COSVR118 Thatch structures



Overview

This standard is about

- 1 interpreting information
- 2 adopting safe and healthy working practices
- 3 selecting materials, components and equipment
- 4 thatching the main coatwork and forming eaves, gables and ridge work

COSVR118 Thatch structures

Performance criteria

You must be able to:

- P1 interpret the given information relating to the work and resources to confirm its relevance
- P2 comply with the given, relevant legislation and official guidance to carry out your work and maintain safe and healthy work practices
- P3 select the required quantity and quality of resources for the methods of work
- P4 comply with organisational procedures to minimise the risk of damage to the work and surrounding area
- P5 comply with the given contract information to carry out the work efficiently to the required specification
- P6 complete the work within the allocated time, in accordance with the programme of work

Thatch structures

Knowledge and understanding

Performance Criteria 1

Interpretation of information

You need to know and understand:

- K1 the organisational procedures developed to report and rectify inappropriate information and unsuitable resources, and how they are implemented
- K2 the types of **information**, their source and how they are interpreted
- K3 the organisational procedures to solve **problems** with the **information** and why it is important they are followed

Performance Criteria 2

Safe work practices

You need to know and understand:

- K4 the level of understanding operatives must have of **information** for relevant, current **legislation and official guidance** and how it is applied
- K5 the types of fire extinguishers and how and when they are used
- K6 how emergencies should be responded to and who should respond
- K7 the organisational **security procedures** for tools, equipment and personal belongings
- K8 what the accident reporting procedures are and who is responsible for making the report
- K9 why, when and how healthy and safety control equipment should be used

Performance Criteria 3

Selection of resources

You need to know and understand:

- K10 the characteristics, quality, uses, sustainability, limitations and defects associated with the **resources** and how defects should be rectified
- K11 how the **resources** should be used and how any **problems** associated with the **resources** are reported
- K12 the organisational procedures to select **resources**, why they have been developed and how they are used
- K13 the **hazards** associated with the **resources** and **methods of work** and how they are overcome

Thatch structures

| | Performance Criteria 4 |
|----------------------------------|---|
| | Minimise the risk of damage |
| You need to know and understand: | K14 how to protect work from damage and the purpose of protection |
| | K15 why disposal of waste should be carried out safely and how it is |
| | achieved |
| | Performance Criteria 5 |
| You need to know and understand: | Meet the contract specification |
| | K16 how methods of work, to meet the specification, are carried out and |
| | problems reported |
| | K17 how maintenance of tools and equipment is carried out |
| | Performance Criteria 6 |
| | Allocated time |
| You need to know and understand: | K18 what the programme is for the work to be carried out in the estimated, |
| | allocated time and why deadlines should be kept |

Thatch structures

Additional Information

Scope/range related to performance criteria

Performance Criteria 1

interpretation of drawings, specifications, method statements, risk assessments, schedules, and manufacturers' information related to the work to be carried out

Performance Criteria 2

- 2 avoidance of risk by complying with the given information relating to the following
 - 2.1 methods of work
 - 2.2 safe use of health and safety control equipment
 - 2.3 safe use of access equipment
 - 2.4 safe use and storage of materials, tools and equipment
 - 2.5 specific risks to health

Performance Criteria 3

- 3 selection of resources associated with own work
 - 3.1 materials, components and fixings
 - 3.2 tools and equipment

Performance Criteria 4

- 4 protection of the work and its surrounding area from damage
- 5 minimise damage and maintain a clean work space
- 6 disposal of waste in accordance with current legislation

Performance Criteria 5

- 7 demonstration of work skills to measure, mark out, fit, position, secure and finish
- 8 use and maintain hand tools, portable power tools and ancillary equipment
- 9 thatch structures to form main coatwork, eaves, gables and ridge work, to given working instructions, to provide a surface to prevent the penetration of water using at least one of the following
 - 9.1 long straw variants (cereal straw
 - 9.2 combed wheat reed (cereal straw)
 - 9.3 water reed,
 - 9.4 specialist materials: sedge grass, heather, marram, bent, bracken, rush, flax, turf or others

10 prepare spars, sways and liggers

COSVR118 Thatch structures

Performance Criteria 6

11 completion of own work within the estimated, allocated time to meet the needs of other occupations and/or client

Thatch structures

Scope/range related to knowledge and understanding

Disposal of waste

1 environmental responsibilities, organisational procedures, manufacturers' information, statutory regulations and official guidance

Emergencies

- 2 operative's response to situations in accordance with organisational authorisation and personal skills when involved with
 - 2.1 fires, spillages, injuries
 - 2.2 emergencies relating to occupational activities

Fire extinguishers

3 water, CO₂, foam, powder and their uses

Hazards

4 those identified by risk assessment, method of work, manufacturers' technical information, statutory regulations and official guidance

Health and safety control equipment

- 5 identified by the principles of protection for occupational use, types and purpose of each type, work situations and general work environment
 - 5.1 collective protective measures
 - 5.2 personal protective equipment (PPE)
 - 5.3 respiratory protective equipment (RPE)
 - 5.4 local exhaust ventilation (LEV)

Information

6 drawings, specifications, schedules, method statements, risk assessments, manufacturers' information and current regulations governing buildings and associated with historical conservation for thatching structures

Legislation and official guidance

7 this relates to the operative's responsibilities regarding potential accidents and health hazards whilst working in the workplace, at height, in confined spaces, with tools and equipment, with materials and substances, with movement/storage of materials and by manual handling and mechanical lifting

Maintenance

8 operative care of hand tools and/or portable power tools and ancillary equipment

Thatch structures

Methods of work

- 9 application of knowledge for safe and healthy work practices, procedures and skills relating to the method/area of work and materials used to:
 - 9.1 thatch structures with long straw variants (cereal straw)
 - 9.2 thatch structures with combed wheat reed, (cereal straw)
 - 9.3 thatch structures with water reed
 - 9.4 thatch structures with specialist materials: sedge grass, heather, marram, bent, bracken, rush, flax and turf or other suitable material
 - 9.5 prepare spars, sways and liggers
 - 9.6 use thatching materials to form main coatwork, eaves, gables and ridge work
 - 9.7 form joins with other materials and abutments
 - 9.8 ensure thickness and depth of thatch materials will provide optimum long term performance
 - 9.9 position fixings to secure and maintain the integrity of the thatch (depth and spacing)
 - 9.10 apply fire prevention measures
 - 9.11 work on buildings of historical significance
 - 9.12 use hand tools, portable power tools and equipment
 - 9.13 work at height
 - 9.14 use access equipment
- 10 team work and communication
- 11 needs of other occupations associated with thatching

Problems

- 12 those arising from information, resources and methods of work
 - 12.1 own authority to rectify
 - 12.2 organisational reporting procedures

Programme

- 13 types of progress charts, timetables and estimated times
- 14 organisational procedures for reporting circumstances which will affect the work programme

Protect work

15 protect work against damage from general workplace activities, other occupations and adverse weather conditions

Thatch structures

Resources

- 16 materials, components and equipment relating to types, quantity, quality, sizes and the sustainability of standard and/or specialist:
 - 16.1 thatch materials: cereal straw (long straw variants, combed wheat reed), water reed
 - 16.2 specialist materials: sedge grass, heather, marram, bent, bracken, rush, flax and turf or other suitable material
 - 16.3 coppice materials (spars, sways and liggers)
 - 16.4 netting
 - 16.5 lead
 - 16.6 mortar
 - 16.7 fixings and ancillary items
 - 16.8 hand and/or portable powered tools and equipment
- 17 methods of calculating quantity, length, area and wastage associated with the method/procedure to thatch roof structures

Security procedures

18 site, workplace, company and operative

Thatch structures

| Developed by | ConstructionSkills |
|--------------------------|---|
| Version number | 2 |
| Date approved | October 2012 |
| Indicative review date | October 2017 |
| Validity | Current |
| Status | Original |
| Originating organisation | ConstructionSkills |
| Original URN | VR118 |
| Relevant occupations | Roofers, Roof Tilers and Slaters |
| Suite | Roofing Occupations (Construction); Heritage Skills (Construction) |
| Key words | Thatcher; Long straw; Combed wheat reed; Water reed, Sedge grass; Coppice material; Heather; Marram; Bent; Bracken; Rush; Flax; Turf; Spars; Sways; Liggers |